

Installation requirements:

Lincoln County Rural Water System, Inc. requires appointments be scheduled 24 hours in advance of meter pit, service line installation. Appointments between the hours of 8:30am to 4:00pm, Monday through Friday, to be set up with System office. Telephone number 605 767 2966.

The excavation site for the meter pit shall be a maximum of 72 inches to the bottom of the trench. Two 4 inch x 8 inch x 16 inch concrete blocks shall be installed on the flat, level surface under the meter pit. ¼ to ¾ inch pink quartzite shall be installed under the meter pit and to a depth of 6 inches around the outside of the meter pit. The meter pit shall be plumb during backfill and level when backfill is complete. Even lifts are required, while backfilling and compacting, to prevent egg-shaping the meter pit.

A 2 inch x 3 inch x 6 inch concrete brick shall be installed under the inlet and outlet of the meter pit to support the fittings from downward pressure from backfill.

A 4 inch x 6 inch x 6 inch concrete block shall be installed under the curb stop valve, and the curb stop riser shall be plump and straight when back fill is complete. A minimum of 8 mil LLDPE poly wrap shall cover all exposed surfaces of the curb box riser.

Signature of contractor

Date

Signature of LCRWS authorized inspector